

BOARD OF COUNTY COMMISSIONERS
ESCAMBIA COUNTY, FLORIDA

OFFICE OF PURCHASING

213 PALAFOX PLACE, 2nd Floor
P.O. BOX 1591
PENSACOLA, FL 32591-1591
TELEPHONE (850)595-4980
(SUNCOM) 695-4980
(850)595-4805

<http://www.myscambia.com/departments/purchasing>



CLAUDIA SIMMONS
Purchasing Manager

December 12, 2011

To: All Known Bidders

ADDENDUM NUMBER 2:

Re: **Escambia County Sheriff's Office Warrington Precinct
Specification Number PD 11-12.003**

Bidders:

We recently sent you an Invitation to Bid on the above mentioned specification.

This Addendum #2 provides for the following:

**YOU MAY OBTAIN THE INFORMATION CONTAINED ON THE DISC AT THE OFFICE OF
PURCHASING, 213 Palafox Place, Pensacola, FL 32502**

The following items are added, or modified as noted:

1. Spec Section 101100: Visual Display Surfaces – Provide One board for Room 134 that is magnetic and 16'W x 4'H.
2. Spec Section 102113: Toilet Compartments – Please provided Full Length Stainless Steel Brackets. Remove Reference to Stirrup Brackets. In addition, please remove reference to Plastic Laminate Partitions and replace with Solid Plastic Partitions. Color to be Hunter Green or selected equal.
3. Spec Section 102800: Toilet Accessories - A&J will be an acceptable alternate.
4. Spec Section 104413: Fire Extinguishers, Cabinets, and Accessories – Provide 2 Fire Extinguishers with semi – recessed fire extinguisher cabinets for each Fire Extinguisher provided. One within room 134 and one within Room 121 24" to the right of the strike side Door 119 at standard mounting height.
5. Spec Section 107500: Flagpoles – Please provide a cone tapered Flagpole with an internal halyard. Remove reference to the entasis tapered flagpole (10 75 00 2.2 B) and change to cone tapered flagpole. In addition, delete reference to external halyard system. The cam cleat and cylinder lock for the door will be required. Remove section 2.2 G.
6. Spec Section 124813: Entrance Floor Mats & Frames – Provide one (1) Entrance Floor Mat in the Lobby Room 101 size 8'x5'. Provide Two (2) other at doors 115 and 116 size 5'x3". All Floor Mats are to be surface mounted. Reference revised specification 12 48 13 Entry Mats (rev2)
7. Sheet A412: SIP Panel Bid Alternate; the drive-way canopy and entry way are to be SIP for the fascia/soffit to be equal around the building.
8. Sheet A12: The ballistic material can not break on the stud and must be joined per manufacturer's directions.
9. Sheet A101: Wall B1 is only to be used where indicated. The ballistic material is only used on those three walls. B1 does not carry through the room 103.

10. Sheet A411: There is 5/8" sheet rock at the underside of the trusses at all interior areas See Sheet A411.
11. Sheet A411: See Sheet A401 for A411 Section locations.
12. Spec Section 07 41 13 Page 3 Section 2.5: Thermal insulation – delete reference to composite insulation See 07 21 00 2.1, spray applied insulation is to be used at underside of plywood roof deck, see sheet A411. For Alternate 01 SIP Panel to be R-30 see addendum 2 item 30 for additional information.
13. Sheet A501: Doors 115, 116, and 121 are to be Level 8 ballistic rated. All entrance storefront (including glass) into Waiting Room 101 is to be Level 8 Ballistic rated. Reference sheet A501 door schedule, Door 101 to be pair 3'0x7'0 (see attached Entrance Storefront, ASI-001 for dimensions). Interior doors 103B and 131 are required to be Level 8 ballistic rated.
14. All Furniture shown on sheet A131 is owner provided/installed.
15. Sheet S-102: Block all plywood joints as indicated in roof framing notes and legend.
16. All ductwork is to be between the ACT ceiling and the sheetrock at the bottom chord of the truss. Reference sheet 3/A401
17. Sheet A701: Monument Sign letters are to be on both sides of the sign. They are aluminum letters per specification attached to the brick. There is no backing material. The Sheriff's Star is to be in color. The Sheriff David Morgan portion of the sign will be made up Plastic Injection Molded Architectural Letters with a Centra Board backing that is removable. The backing board is to be 5'x 6". (See Attached, Monument Sign ASI-007).
18. Sheet A411: 5/8" Gypsum Board at Truss Chord: Reference Maximum Framing Spacing in standard in National Gypsum Wallboard Products for 5/8" Single Layer. Sheets are to be run Perpendicular to framing and fastener spacing not to exceed 24" on center. Blocking will required where the 24" max spacing is not maintained.
19. Sheet A521: Interior Door and Frame 106 – The frame is to be hollow metal. The door dimensions are incorrect. Reference sheet A501 door schedule; door 106 to be 3'0x7'0 with Hollow Metal frame. The door is a Solid Core wood flush 20 min door with Full Glass Lite. All glass is to tempered wire glass. See Attached sheet Asst. Storefront, ASI-002
20. Spec Section 04 23 00 – Glass Block Specification is added (see attached 04 23 00 Glass Block (rev 2)).
21. Sheet A141 – VCT Floor Pattern – . Colors are to be revised to the following: Camel Beige 51805, Washed Linen 51810, and Tea Garden Green 51872. (See attached sheets: VCT Muster ASI-003, VCT Lobby ASI-004, and VCT Hallway ASI-005).
22. Spec Section 10 28 00 – See Sheet A111 for Tile Layout of Shower. It is not a prefabricated unit. Accessories are to be provided separately. There will be three robe hooks provided per Restroom. One (1) located in the toilet rooms, and two (2) located outside the shower. One at standard height and one at the ADA required height.
23. Spec Section 10 14 00 – Paragraph 2.4 – Panel Signs/Interior Signs. (See attached Interior Sign ASI-006, also see attached Plaques ASI – 008)
24. Sheet A501: All interior doors are solid core flush wood doors. Reference specification section 08 14 16
25. Sheet A101: Rooms 124 and 125 – Handicap Stall Door is to be provided by Toilet Partition manufacturer. See item # 2 on this document and reference specification section 10 21 13.
26. Spec Section 03 13 00 – Insulated Concrete Forms: The following are approved equals; Reward Wall Systems (www.rewardwalls.com), Amvic System (www.amvicsystem.com), Fox Block (www.foxblocks.com).
27. Sheet A411 – Arriscraft – Provide Arriscraft size 12x24 units. Please provide the finished ends at all corners and door jambs. This will apply to the split face alternate as well. We will require split face returns. Do not mitre any corners.

28. Sheet A111 – Shower Dimension and Tile: Please use the dimensions on the floor plan. Showers are the only locations to receive wall tile. With regards to the sidewalls of the shower, the wall tile will stop at the threshold of the shower.
29. Spec Section 10 14 00 Paragraph 2.2 – Plaques. See Sheet ASI 008. Location to be determined.
30. Sheet A412 Section 1 – SIP Uplift/Detail – The manufacturer will provide the fastening schedule and information for the panels based on the uplift that has been stated in the drawings (ref sheet S-002). SIP panel design to be engineered (signed and sealed per Florida Regulations) by SIP manufacturer.
31. Hardware Specification In Addendum 1 is correct and should have read Revision 2. See attached Hardware Specification 08 71 00 Revision 2. (Note: same as issued in addendum 1 except for Revision number).
32. Provide a 4'x8' plywood construction sign per county standard.
33. See attached "Bid Form for Addenda 2" Bid form revised to provide Alternate 5. The alternate provides for a completion schedule of 180 days for substantial completion and 210 for final completion. The base bid remains 210 days for substantial completion and 240 days for final completion.
34. Reference C101. Owner information: Owner is School Board of Escambia County. Escambia County is the lessee of the property. Escambia County will be contracting entity.

This Addendum Number 2 is furnished to all known prospective bidders. Please sign and return one copy of this Addendum, with original signature, with your bid as an acknowledgement of your having received same. You may photo copy for your record.

Sincerely,



Paul Nobles, CPPO, CPPB
Purchasing Coordinator

SIGNED: _____

COMPANY: _____

PN/lk